

To:	David Ailles	From:	Darryl Hern, P.Eng
	York Developments		Stantec London
File:	161414170	Date:	January 9, 2024

Reference: Westwinds Subdivision Sanitary Capacity

This memo is compiled to confirm the sewer system within the W3 Subdivision and Sunset Creek Subdivision have the sanitary capacity within this system to permit the density requested from the Westwinds Subdivision.

The Westwinds Subdivision, with lies adjacent to the northeast of the W3 Subdivision has been included in the design of the sanitary sewer system within the W3 Subdivision, specifically W3 Phase 2.

Stantec has included the population densities as outlined in the chart below and included on the attached design sheet and External Sanitary Area plan. The Westwinds Subdivision would contribute to the sanitary sewers along Royal Magnolia Avenue and, under the ultimate scenario, when the sewer is connected to the Colonel Talbot Pumping station there is adequate capacity to accommodate the Westwinds Subdivision's flows.

	ULT	1 —	POPULAT	ION CALC	ULATION	
	ZONING	AREA (ha)	UNITS	POP/ha	POP/units	POP.
	MED DENSITY	10.15	_	180	-	1827
	ROADS	2.61	—	_	-	—
		16.19	BLOCKS 1, 1A, 2, 3, 4	LOW DENSITY	3/46	138
			BLOCKS 5, 7	MED DENSITY	2.4/24	58
	WESTWINDS		BLOCKS 6, 9, 10	APT & TOWNHOUSE	2.4/24 1.6/984	1632
	SUBDIVISION		BLOCK 8	MED DENSITY	1.6/108	173
			BLOCK 11	MED DENSITY	1.6/130	208
			BLOCK 12	MED DENSITY	2.4/16 1.6/115	222
	TOTAL	28.95	_	_	_	4258

Stantec added these populations into the design sheet for W3 Phase 2 (attached) and can confirm that the pipes are sized to adequately handle the sanitary flows from the Westwinds Subdivision as well as the W3 Subdivision with the total flows not exceeding the downstream pipe's capacity.


January 9, 2024

David Ailles Page 2 of 2

Reference: Westwinds Subdivision Sanitary Capacity

We trust this clarifies the required sanitary capacities for the areas outlined above. If you require anything further, please contact the undersigned.

Sincerely,



Stantec Consulting Ltd.

Darryl Hern, P.Eng.

Phone: 519-675-6622 Fax: 519-645-6575 darryl.hern@stantec.com

Attachment: W3 Subdivision Phase 2 - Sanitary Design Sheet W3 Subdivision Phase 2 - External Sanitary Drainage Area Plan

c. C.C. Mike Meddaoui - Westwinds

RESIDENTIAL COMMERCIAL AND INSTITUTIONAL POPULATION DENSITIES

THE FOLLOWING POPULATION ALLOWANCES WILL APPLY WHEN DESIGNING SANITARY SEWERS: = 30 UNITS / HECTARE @ 3 PEOPLE / UNIT

LOW DENSITY (SINGLE-FAMILY / SEMI-DETACHED)

MEDIUM DENSITY (MULTI-FAMILY / TOWNHOUSE / ROWHOUSE)

HIGH DENSITY (APARTMENTS) COMMERCIAL / INSTITUTIONAL SECONDARY SCHOOL

= 75 UNITS / HECTARE @ 2.4 PEOPLE / UNIT

= 150 - 300 UNIT / HECTARE @ 1.6 PEOPLE / UNIT = 100 PEOPLE / HECTARE

= 1500 PEOPLE

= 600 PEOPLE

ELEMENTARY SCHOOL

LOCATION			AREA			POPULATION			SEWAGE FLOWS				SEWER DESIGN							
		FROM	ТО		DELTA HECTARE	TOTAL	POP. PER		NO. OF	DELTA	TOTAL	PEAKING	INFILT	SEWAGE	Q TOTAL	PIPE SIZE		SLOPE	САР	VELOCI
AREA No.	STREET NAME		MANHOLE	GROSS	S	HECTARES	HECTARE	PER LOT	LOTS	POP.	POP.	FACTOR	L/s	L/s	L/s	mm	n	%	L/s	m/s
EXT 1	ROYAL MAGNOLIA AVENUE	(TOP)	S114	N	28.95	28.95				4258	4258	3.31	2.90	41.26	44.15					
EXT A216	ROYAL MAGNOLIA AVENUE	S114	S113	N	0.30	29.25		2.4	14	32	4290	3.31	2.93	41.53	44.46	300	0.013	0.30	53.0	0.75
EXT A217	ROYAL MAGNOLIA AVENUE	S113	S106	N	0.50	29.75		2.4	23	54	4344	3.30	2.98	41.99	44.97	300	0.013	0.30	53.0	0.75
EXT A215	ROYAL MAGNOLIA AVENUE	CAP2	S106	N	2.02	2.02				600	600	3.93	0.20	6.91	7.11	200	0.013	1.30	37.4	1.19
A218	ROYAL MAGNOLIA AVENUE	S106	S105	N	0.17	31.94				0	4944	3.25	3.19	47.05	50.24	300	0.013	0.30	53.0	0.75
A214	ROYAL MAGNOLIA AVENUE	(TOP)	S105	N	1.18	1.18				0	0	4.50	0.12	0.00	0.12					<u> </u>
A219	FUT. STREET L	(TOP)	S105	N	0.08	0.08				0	0	4.50	0.01	0.00	0.01					
A206	ROYAL MAGNOLIA AVENUE	S105	S104	N	0.38	33.58		3	5	15	4959	3.25	3.36	47.17	50.53	300	0.013	0.30	53.0	0.75
A207	DARWIN CRESCENT	S107	S104	N	0.36	0.36		3	5	15	15	4.40	0.04	0.19	0.23	200	0.013	1.30	37.4	1.19
A205	ROYAL MAGNOLIA AVENUE	S104	S103	N	0.58	34.52		3	11	33	5007	3.24	3.45	47.57	51.02	300	0.013	0.30	53.0	0.75
A204	ROYAL MAGNOLIA AVENUE	S103	S102	N	0.90	35.42		3	18	54	5061	3.24	3.54	48.02	51.56	300	0.013	0.30	53.0	0.75
A203	ROYAL MAGNOLIA AVENUE	S102	S101	N	0.87	36.29		3	17	51	5112	3.24	3.63	48.44	52.07	300	0.013	0.30	53.0	0.75
A208	DARWIN CRESCENT	S107	S108	N	0.39	0.39		3	6	18	18	4.39	0.04	0.23	0.27	200	0.013	1.00	32.8	1.04
A209	DARWIN CRESCENT	S108	S109	N	0.52	0.91		3	9	27	45	4.32	0.09	0.57	0.66	200	0.013	1.00	32.8	1.04
A210	DARWIN CRESCENT	S109	S110	N	0.85	1.76		3	14	42	87	4.26	0.18	1.09	1.26	200	0.013	0.55	24.3	0.77
A211	DARWIN CRESCENT	S110	S111	N	0.87	2.63		3	15	45	132	4.21	0.26	1.63	1.89	200	0.013	0.55	24.3	0.77
A212	DARWIN CRESCENT	S111	S112	N	0.40	3.03		3	6	18	150	4.19	0.30	1.84	2.14	200	0.013	0.55	24.3	0.77
A213	DARWIN CRESCENT	S112	S101	N	0.36	3.39		3	5	15	165	4.18	0.34	2.02	2.36	200	0.013	0.55	24.3	0.77
A202	ROYAL MAGNOLIA AVENUE	S101	САР	N	0.27	39.95		3	4	12	5289	3.22	4.00	49.91	53.90	300	0.013	0.40	61.2	0.87
A202	ROYAL MAGNOLIA AVENUE	CAP	EX S1	N	0.00	39.95				0	5289	3.22	4.00	49.91	53.90	300	0.013	0.40	61.2	0.87
A201	ROYAL MAGNOLIA AVENUE	EX S1	EX S2	Ν	0.32	40.27		3	6	18	5307	3.22	4.03	50.06	54.08	300	0.013	0.50	68.4	0.97

STANTEC STANTEC STANTEC

STANTEC

EXISTING SERVICES	DRAWING #, SOURCE	DATE	CONSTRUCTED SERVICES	COMPLETION	DET	DETAILS		REVISIONS	DATE	
					DESIGN	DESIGN CHK		AS PER 1ST SUBMISSION COMMENTS	FEB 2023	
					DRAWN BY	СНК	2.	AS PER 2ND SUBMISSION COMMENTS	JUNE 2023	
					CHECKED	DWH	3.	AS PER 3RD SUBMISSION COMMENTS	SEPT 2023	
					APPROVED	APPROVED DWH		AS PER 4TH SUBMISSION COMMENTS	DEC 2023	
					DATE	APRIL 2022				
					Γ					

SANITARY SEWER DESIGN SHEET CITY OF LONDON

PROJECT NAME:

W3 SUBDIVISION PHASE 2

DESIGN CRITERIA SEWAGE = 230 LITRE / CAPITA / DAY INFILTRATION = 8640 LITRES / HECT PEAKING FACTOF 1 + 14 4 + P ^ 0.5 (TOP) = TOP END OF SEWER TRIBU






ENGINEER'S STAMP

AY CTARE / DAY			DATE: DESIGNED B	Y:	Sep-23 CHK					
JTARY	/									
			PROJECT FIL	E NO.	1614	14170				
				PROFILE						
					INVERT EI	EVATION				
CITY s	LENGTH m	FALL IN SEWER	HEADLOSS IN U.S. MH	DROP IN MANHOLE	U.S.	D.S.				
'5	62.1	0.186	-	-	267.119	266.933				
'5	69.0	0.207	-	0.030	266.903	266.696				
9	9.2	0.120	-	-	267.120	267.000				
'5	57.6	0.173	-	0.030	266.666	266.493				
, <u> </u>	70.0	0.000			000 400	000 005				
'5	76.0	0.228	-	-	266.463	266.235				
9	74.0	0.962			269.800	268.838				
9	74.0	0.902	-	-	209.000	200.030				
'5	67.9	0.204	_	_	266.205	266.001				
'5	97.1	0.291	-	0.030	265.971	265.680				
'5	98.0	0.294	-	0.030	265.650	265.356				
)4	18.0	0.180	-	_	269.800	269.620				
)4	47.8	0.478	-	0.030	269.590	269.112				
'7	96.5	0.531	-	0.030	269.082	268.551				
7	97.2	0.535	-	0.030	268.521	267.987				
7	14.4	0.079	-	0.030	267.957	267.878				
7	77.3	0.425	-	0.030	267.848	267.423				
37	46.5	0.186	-	0.030	265.326	265.140				
37	2.9	0.012	-	0.000	265.140	265.128				
)7	37.8	0.189	-	0.030	265.098	264.909				

SCALE	W3 SUBDIVISION - PHASE 2 W3 LAMBETH FARMS INC.	PROJECT No. 161414170
	sheet No. 5 of 34	
	PART 1	PLAN FILE No.



2										_
cymur (EXISTING SERVICES	DRAWING #, SOURCE	DATE	CONSTRUCTED SERVICES	COMPLETION	DETAILS	No.	REVISIONS	DATE	
ŝ						DESIGN CHK	1.	AS PER 1ST SUBMISSION COMMENTS	FEB 2023	
						DRAWN BY CHK	2.	AS PER 2ND SUBMISSION COMMENTS	JUNE 2023	
						CHECKED DWH	3.	AS PER 3RD SUBMISSION COMMENTS	SEPT 2023	
E						APPROVED DWH	4.	AS PER 4TH SUBMISSION COMMENTS	DEC 2023	
5						DATE APRIL 2022				
1										
-										





ENGINEER'S STAMP

